THE CORPORATION OF THE DISTRICT OF PEACHLAND
REQUEST FOR QUOTE - LINE PAINTING (2015 – 2017)

SCOPE OF WORK

1. Provide all labour and materials required to complete the new and re-painting of all traffic line marking as outlined herein. The District of Peachland is seeking a three year agreement from 2015 through 2017.

2. Provision of traffic control.

3. All line painting over existing to be equal in width and length as found. Line colors and stencils to match existing (100mm wide for centerlines and 75mm wide for shadow lines).

4. Please provide a cost for 2015, 2016 and 2017. Each year should be separated with a total for each year and a total for all three years.

SCHEDULE

Approximate total distances for lane dividing lines are as follows; double yellow = 4.8 km, single Yellow = 11.4 km, single white = 7.2 km. In addition, there are a number of parking spaces and assorted items to be painted. Please note that all distances and quantities provided are approximate and should be confirmed by the contractor.

The successful contractor will be required to provide copies of the following:

1. Liability insurance coverage for a minimum of 2 million dollars (CDN)
2. A current letter of standing / clearance letter from Worksafe BC
3. Must be willing to enter into a Prime Contractor agreement. This agreement indicates that the successful contractor will be responsible for their own occupational health and safety
4. Demonstration of their respective health and safety program
5. Must be willing to sign and agree to abide by the District's Respectful Workplace Policy (attached).

PRIMARY WORK

Traffic dividing lines: Double yellow = 4.8 km, Single Yellow = 11.4 km, Single white = 7.2 km

1. Princeton Avenue	Double yellow	Centre	4.7 km
	Single white	Fog	3.6 km
2. Beach Avenue	Single white	Centre	3.6 km
	Single yellow	Centre	2.7 km
3. 13th Street	Single yellow	Centre	100 m
4. Ponderosa Drive	Single yellow	Centre	2.6 km
5. Trepanier Bench Road	Single yellow	Centre	1.4 km
6. Buchanan Road	Single yellow	Centre	1.0 km
7. Huston Road	Single yellow	Centre	1.4 km
	Single white	LH turn lane	20 m
	Double yellow	LH turn lane	140 m
8. Cousins Road	Single yellow	Centre	900 m
9. Renfrew Road	Single yellow	Centre	1.3 km

B. The following is an approximate summary of the other items that are painted on the surface of our roads, mostly in the downtown area, that is included with the primary work section. This is a current inventory but is subject to change.

White Paint

10	Large X's, to warn of upcoming crosswalks, totalling 15m length each
36	6' letters (3 each of SLOW 30km, and 2 of SCHOOL)
2150 lm	Lines marking parking spots (angle spots)
956 lm	Lines marking parking spots (parallel parking spots, 'T' style)
35	Crosswalks (26 Zebra style, 7 parallel style)
39	Stop bars (located downtown and off of major routes)
4	Directional arrows (5' tall, Robinson Pl)
10	Bike lane stencils (with arrow)

Yellow Paint

441 m 2	Estimate of yellow hashing throughout (+/-)
13	Locations of 2' lettering such as "NO PARKING," "FIRE DEPT," or "MOTORCYCLES OK", BOAT LAUNCH WAITLINE
450m	Yellow curbing (including some driveway accesses along Beach Ave)

OTHER

26	Handicap logos (6' x 6')

PRODUCTS AND EXECUTION

TRAFFIC LINE MARKING PAINT

1. General Paint 78-line Road Marking Paint (or alternate approved manufacturer)

   Air Spray or airless spray application

   One coat application

   Theoretical spreading rate: 40-42 litres/kilometre at 100mm stripe

   Maximum thinning 10% with 05-518 Aromatic thinner Type 2

   Colors: 78-020 White and 78-021 Yellow

2. Apply traffic line marking paint in strict accordance to manufacturer's specified application instructions. Inspect all surfaces to ensure new application is compatible with existing. Remove any loose surface material to ensure positive bonding of new paint. All surfaces must be clean and dry upon application. Apply in temperatures not less than 4 degrees Celsius. Protect adjacent surfaces of public and private property from damage caused by cleaning and/or overspray of materials. Be responsible for any damages incurred as a result of this work.

3. Glass bead overlay shall be included in the proposed prices.

TRAFFIC CONTROL AND PROTECTION

1. During the course of the work, provide sufficient personnel, barriers and traffic control devices to protect the public. Provide temporary cones, barricades and/or flag persons required to protect line marking during the required drying period (minimum 30 min). Complete sections of painting such as at crosswalks in two applications so as to not interrupt the flow of traffic and maintain safety.

2. Painting may be completed during evenings or at night provided the work is completed in strict accordance with Municipal Bylaws and with sufficient light to ensure a neat and uniform application. Overspray will not be accepted.

3. Upon completion of the work, clean-up all materials and equipment from the course of this work and remove from site. Disposal of all materials to be in strict accordance with local bylaws and in accordance with all applicable provincial statutes.

SCOPE OF WORK

Please provide a cost for the completion of all the outlined works in a lump sum price that is all inclusive of all costs with providing this service. In addition, please include prices for the removal of any paint that we deem no longer necessary. Your quote should include the prices for 2015, 2016 and 2017, a three year agreement.

All extra work that is approved by the Director of Operations will be at an hourly rate. Please provide hourly costs. **All primary works for 2015 are to be completed by May 8th, 2015.**

Please forward all questions to

Shawn Grundy – Operations Leadhand
District of Peachland

Phone (250) 767-2108
Cell (250) 718-0806
Fax (250) 767-6370

e-mail: sgrundy@peachland.ca

Quotes are due by 2:00 PM, April 15, 2015
Fax to: 250.767.3433
Email Quote to the Executive Assistant: executiveassistant@peachland.ca